

## JLX® Self-Leveling 180° Cross-Line Laser with GreenBrite® Technology

**Model #:** 40-6681

**UPC:** 049448066810



Johnson crafted the JLX® series of products to meet the demands and exceed the expectations of professionals, and the 40-6681 is no exception. It features GreenBrite® technology, making the beam 400% more visible than red beams for working in sunny or brightly lit conditions. It projects a cross-line with 180° coverage on the horizontal beam. With the included magnetic base, magnetic target, Lithium Ion battery and charger, and alkaline battery compartment, this kit comes with everything you'll need to get your job up and running!

## **PRODUCT DETAILS**

40-6681 Includes > Green laser with magnetic base, magnetic target, li-ion battery and charger, alkaline battery compartment (alkaline batteries not included), hard-shell carrying case

- GreenBrite® Technology 400% more visible than red lasers
- Includes li-ion rechargeable battery pack
- Cross-line with 180° coverage on the horizontal beam
- Pulse mode for use with line detector (sold separately)
- Pendulum lock protects laser during transport
- IP54 dust and water resistant construction

## **SPECIFICATIONS**

Accuracy ±1/8"/35'

Battery Life 6 Hours Li-ion

Interior Range Up to 200 ft, (Detector range up to 75 ft. Exterior)

IP Protection Class IP 54
Laser Classification Class IIIa

Laser Wavelength 520nm±10nm (Green)
Leveling Method Self-Leveling (Pendulum)

Maximum Power Output ≤5mW

Power Supply 4 "AA" alkaline batteries (not included); Li-ion rechargable battery pack (included)

Self-Leveling Range ±3°
Tripod Thread 1/4"- 20

Warranty 3 Year Warranty Working Temperature 14°F to 113°F



For additional information on Johnson products, please contact Customer Service at 888.953.8357 or service@johnsonlevel.com www.johnsonlevel.com | © Johnson Level & Tool Mfg. Co. Inc.



## **APPLICATION**

Johnson's 40-6681 is a versatile tool that you'll find useful for any number of leveling project, such as hanging shelving and pictures, tiling walls, leveling cabinets, finish work, flooring, drywall track/stud wall installation and more.

